

# SERVICE PROTECTION FOR SITE DEMOLITION

1. Prior to any demolition work the Owner / Contractor shall complete one of the following:
  - a) Submit a request to the Public Works Department to have any existing water meters pulled. Water Meters may only be removed by the Water Division.
  - b) Owner's contractor shall install a riser / stand pipe per detail hereon.
2. A minimum of 24 hours prior to any demolition work the Owner or Contractor shall request an inspection from the Water Division to verify water meter was pulled per request or a riser / stand pipe was installed and meets minimum requirements. No demolition work is allowed until compliance with these requirements are verified by the Water Division Inspector.
3. Hoses connected to the riser / stand pipe may not be connected to storage tanks, be submerged or used in any manner inappropriate for use with the atmospheric vacuum breaker.
4. For areas with no sidewalk, riser / stand pipe shall be placed a maximum of 12" behind water meter box.
5. Contractor shall provide barricades or other suitable protection for riser / stand pipe.

Approved by: *BS [Signature]* 12-29-06 Date  
 City Engineer R.C.E. 14527

Drawn by: JSWilliams Date: December 19, 2006  
 Revised by: Date:  
 Effective Date: January 9, 2007

